

Slag Test Certificate

Final

845 Stockwell Road, Angaston SA 5353

PO Box 229, Angaston SA 5353

T: +61 8 8561 3100

F: +61 8 8564 3019

www.adbri.com.au

Product Certified: Ground Granulated Blast Furnace Slag
Test Certificate Number: 240155
Customer: Adbri Cement, Angaston Plant, SA
Sample Code: B0a4133
Sample Date: 24/11/2023

Nominal Blend	Requirements	Result
Ground Granulated Iron Blast-Furnace Slag		>95 %
Calcium Sulphate		<5 %
Other Additions		<0.5 %

Reportable Property	Test Method	Requirements of AS3582.2	Result
Alumina (Al ₂ O ₃)	AS2350.2	Max 18.0 %	13.1 %
Total Iron (FeO)	AS2350.2	N/R	0.7 %
Magnesia (MgO)	AS2350.2	Max 15.0 %	5.9 %
Total Alkali (Na ₂ O Equivalent)	AS2350.2	N/R	0.5 %
Manganese (MnO)	ASTM C114	N/R	0.2 %
Sulfate (as SO ₃) content	AS3583.8	N/R	1.3 %
Sulfide Sulfur (S)	AS3583.7	Max 1.5 %	0.7 %
Chloride Ion Content	AS3583.13	Max 0.1 %	0.029 %
Loss on Ignition	AS3583.3	N/R	-0.4 %
Insoluble Residue	AS3583.14	N/R	0.2 %
45 µm Residue	AS3583.1	N/R	97 % passing
Relative Density	AS3583.5	N/R	2.84
Relative Water Requirement	AS3583.6	N/R	101 %
Strength Index	AS3583.6	N/R	101 %
Other Properties			
SiO ₂	AS2350.2	N/R	33.5 %
CaO	AS2350.2	N/R	43.3 %
Fineness Index	AS/NZS2350.8	N/R	405 m ² /kg

This document shall not be reproduced except in full.

REMARKS


These test results apply specifically to the above designated sample as received at the Adbri Cement Birkenhead Laboratory (Accredited number: 252), 62 Elder Rd Birkenhead SA 5015.

For Relative Water and Strength Index testing the reference control used is Birkenhead GP code B0a4c04.

N/R = No Requirement



Accredited for compliance with ISO/IEC
 17025 - Testing.



Approved Signatory

M. Wythe

Issue Date: 22/03/2024